

Webel

WEST BENGAL ELECTRONICS INDUSTRY DEVELOPMENT
CORPORATION LIMITED.

TENDER DOCUMENT

Miscellaneous rearrangement & repairing works within office and store
room at roof in WECS building

Price Rs.0

Webel

WEST BENGAL ELECTRONICS INDUSTRY
DEVELOPMENT CORPORATION LIMITED

NIT No.: EC/ 07/ WECS/ Misc. repairing/ 2020-21/ 007, dated. 12.08.2020

Sealed Tenders are invited from reputed contractors for the following:

- Name of Work : **Miscellaneous rearrangement & repairing works within office & store room at roof in WECS building**
- Estimated Cost : Rs. 56700/- (approx.)
- Time allowed for completion : 07 (seven) days from the date of issue of Work Order.
- Cost of tender documents : Rs. 0/- (Nil) ~~per tender document in the form of Demand Draft/Pay Order (non refundable) in favour of WBEIDC LIMITED. The same has to be submitted inside the envelope containing Tender on scheduled date.~~
- Earnest Money Deposit : Rs. 0/- (Nil)
- Eligibility of the Contractor** : 1. Contractor should have valid Trade License, P.F, ESI, GST registration (regular & mandatory), PAN No.
2. Contractor should have credential with proper completion certificate of executing similar civil repairing/maintenance works within any office/commercial/industrial building premises in **a single job, of minimum value Rs. 45360/- or two jobs with each of value minimum Rs. 28350/-** under Govt., Semi-Govt., PSU or reputed private companies during last 5 years.

- Last date and time of receipt of tenders : Up to 3.00 P.M on **19/08/2020**
- Address at which the tenders are to be submitted : West Bengal Electronics Industry Development Corporation Ltd. (Webel), ID & M Dept.
Webel Bhavan, Block : EP & GP, Sector-V
Kolkata 700 091.
- Date and time of opening of ~~cover-I~~ of tender : 3.30 P.M on **19/08/2020**
- Place of opening tenders : At the above mentioned venue of tender submission.
- Defects Liability Period : 12 months from the date of virtual completion of work.
- Validity of offer : For a period of 180 days from the date of opening of tender.

Tender will have to be submitted in one part only in single envelope, ~~two parts i.e. Cover-I and Cover-II separately~~, sealed and super scribed with the name of the work.

~~**Cover-I:** Forwarding letter, Signed sealed copies of all aforesaid credential and statutory documents, Record Notes of Pre bid meeting duly signed and stamped, the earnest money in required form. **Cover-I of only those Tenderers who will submit cost of Tender Document as above will be opened.**~~

~~**Cover-II:** Shall contain the offered price with the full Tender Document duly filled. No other condition stipulated in Cover II, other than unconditional general rebate, shall be accepted. **All pages of the Tender Document should have original signature with official seal of the tenderer.**~~

Tender will be opened **on 19/08/2020 at 3.30 P.M** in presence of WBEIDCL officials ~~for only those Tenderers who will submit cost of Tender Document as above.~~

~~**After examining the Cover-I of the tender, WEBEL will open the Cover-II of only those eligible tenderers who have satisfied the requirements of Cover-I. The scheduled date and time of opening of tender cover-II will be intimated to eligible tenderers in due course.**~~

In case the date of opening of tenders is declared as a holiday, the tenders will be opened on the next working day at the same time or will be intimated by WEBEL.

The authority reserves the right to accept or to reject any or all part of this tender at any point of time without assigning any reason what so ever.

Webel

WEST BENGAL ELECTRONICS INDUSTRY
DEVELOPMENT CORPORATION LIMITED

NIT No.: EC/ 07/ WECS/ Misc repairing/ 2020-21/ 007, dated. 12.08.2020

SUBMISSION OF BID

- A.i) Tender shall be submitted along with Tender Fee, ~~Earnest Money Deposit~~ and other requisite documents in sealed envelope ~~as cover I & cover II~~ super scribed thereon name of the work.
- ii) All pages of original Tender document and schedule of quantities should be signed with official seal.
- B. Covering letter and other detail documents should form part of the offer.

C. QUOTING OF RATE FOR PRICED ITEM OF WORK:

The tenderer is requested to go through all the terms and conditions meticulously specified hereinafter before quoting their specific rate. All the quoted rates must be written by hand of the person signing the tender and with same pen and ink. Erasing or over writing will not be allowed under any circumstances. However, correction, if any, will be allowed if it has been duly signed and sealed.

GENERAL TERMS & CONDITIONS

1. The work should be completed within 07 (seven) days from the date of issue of the Letter of Intent/ Work Order.
2. Time is the essence of the contract. If the Contractor delay in the progress of work due to circumstances beyond their control, they shall have to apply in writing with proper justification for the delay to the Corporation for extension of time of completion within 3 (three) days of such occurrence but before expiry of stipulated date of completion. The Corporation on such application, may grant the extension of time. If they think it justified after proper enquiries. However, the finding of the corporation will be final and has to be abided by the Contractor.
3. Any extra work of the items not included in the Schedule scope of work with Bill of quantities will be done on extra item basis and the rate of payment for those extra item/items, if any, will be finalized mutually of the basis of the following in order of preference.
 - a) Rate should be obtained from current PWD Schedule of Rates of presidency Circle.
 - b) Rates derived from similar items of work from PWD Schedule of Rates of presidency Circle.
 - c) Analysis of rates as per prevailing market rates of labour and materials. Necessary documents are to be furnished by the Contractor in support of their rates.
4. The Contractor shall be responsible for any injury that might occur to person/s and any damage that may cause towards any Company's property during the course of execution of the work and they will be liable to make good the same at their cost.
5. The work should be carried out as per PWD Specification and in accordance with the Indian Standard Code of Practice. The materials, which will be used in the work, should have prior approval of the Corporation.
6. The materials, which will be used in the work, should have prior approval of the Corporation.
7. Income Tax deduction will be made at source as per laid down rules of Ministry of Finance.
8. The Contractor shall have to comply with the provisions of all Labour Rules, Wages Act and 1948 Worker's Compensation Act, whichever is application.
9. The Contractor shall have to provide everything necessary for proper execution of the work including labour, tools & tackles and stores etc.
10. The rate quoted by the contractor shall be firm throughout the tenure of the contract and shall be inclusive of all taxes, octroi and other statutory payments and will not subject to any fluctuation due to any increase in any effect.
11. The payment of bill will be made on actual measurement basis against R/A bills and Final Bill. Bills may be paid with part rate against individual items. However, part rates have to be certified by ID & M Dept. of the Corporation.
12. 10% Security Deposit and 1 % labour welfare cess would be deducted from the bill amount. The Security Deposit would be refunded back after maintaining 12 (twelve) months defect liability period from the satisfactory completion of the work. However, the Contractor can submit Bank Guarantee valued 10% of the job as security deposit in

order to get relaxation from any deduction on account of security deposit from the bills.

13. The following materials would not be supplied by the Corporation like brick, cement sand, steel, Plaster of Paris, wood gals, lamination, paint, ceramic tiles, hardware fittings etc. including any other materials needed for execution of the job.
14. The Contractor shall make their own arrangement for storage space and godown for their materials, tools & tackles, Plant & Machinery etc.
15. The Contractor shall not, without the written consent and approval of the Corporation, Sublet any portion of the work.
16. The Contractor shall make their own arrangement for storage space and godown for their materials, tools & tackles, Plant & Machinery etc.
17. Rates of all items should be inclusive of supply of materials, labour charges hire charges of tools & tackles, scaffolding, plant & machinery any taxes and duties etc. In case of only labour involved items, supply of material will not be included.
18. Should the contractor fail to complete the job within the stipulated time as specified in the tender within one extension of time, if permitted, as per clause (10) of the contract will be terminated automatically on the ground of non-completion of work even within the extension of time as permitted in one time and no appeal will be accepted in this respect. The balance job, if any, to be carried out through any other agency at their cost and risk.
19. No other terms and conditions are acceptable from their end if not stipulated in the work order or accepted.
20. **IDLE LABOUR**
No claim for idle labour would be entertained under any circumstances.
21. **COMPLETION DRAWING**
Wherever applicable, the contractor shall have to submit with the final bill, detailed drawings showing the works completed in all respects. Such drawings shall consist of one original and four copies of the same as per instructions of the Engineer-In-Charge.. Unless such drawings are furnished and approved, payment for final bill will not be processed.

Special Terms & Condition

1. Bidders shall submit their bids for the complete scope of work as defined in the tender documents. However, Owner reserves the right to split – up the work, evaluate and award works to one or more Bidders, without prejudice to any provisions made elsewhere in the tender documents.
2. All terms and conditions of the tender documents shall be construed as applicable for any or all parts of the works, in general, unless specifically indicated to the contrary. The provisions as separately applicable in case of sub-division of the works, are set out separately, wherever applicable.
3. The Bidder shall quote prices valid for acceptance by the owner for award of full or part of the works, Bidder shall categorically confirm in their offer, their acceptance to the provisions of this clause.
4. Contract documents for agreement shall be executed after award of works to the successful tenderer by Telegram / Fax / Detailed letter of Intent. Until the final contract documents are prepared and executed this tender document together with the annexed documents, modifications, deletions agreed upon by the Owner and Bidder's acceptance thereof, shall constitute a binding contract between the successful tenderer and the Owner, based on terms contained in the aforesaid documents and the finally submitted and accepted prices.
5. Subject to availability, OWNER will supply power at 400/440V at only one point at the nearest sub-station/source, from where the CONTRACTOR will make his own arrangement of temporary distribution. The point of supply will not be more than 500 Meters away from the CONTRACTOR's site. All the works will be done as per IEA regulations and passed by the ENGINEER – IN – CHARGE. The temporary line will be removed forthwith after the completion of work or if there is any hindrance caused to the other works due to the alignment of these lines, the CONTRACTOR WILL reroute or remove the temporary lines at his own cost. The CONTRACTOR at his cost will also provide suitable electric meters, fuses, switches, etc. for purposes of payment to the OWNER which should be in the custody and control of the OWNER. The cost of power supply be payable to the OWNER every month at Rs.6.00 per Kwh for construction works power which would be deducted from the running account bills. The OWNER shall not, however, guarantee the supply of electricity and no compensation for any failure or short supply of electricity will be entertained.
6.
 - a) The selected agency must pay Earnest Money of requisite amount failing which the tender is liable to be rejected.
 - b.) No interest shall be paid by the OWNER on the Earnest Money deposited by the selected agency.
 - c.) The Earnest Money deposited by selected agency shall be forfeited incase the selected tenderer fails to start work within a period of 10 days.
7. The successful tender shall be issued LOI / LOA. The duplicate copy of the LOA will be returned duly signed by the agency as a token of acceptance. The work order / LOI duly signed by the owner & successful tenderer will be treated as agreement between the parties. In the event of failure on the part of the successful tenderer to sign the work order / LOA within 10 days time from the receipt of the work order / LOA. The earnest money deposit may be forfeited.
8. The work covered by this CONTRACT shall be commenced within 10 days after the receipt of the LETTER OF ACCEPTANCE OF TENDER and be completed in stages on or before the dates as mentioned in the TIME SCHEDULE OF COMPLETION OF WORK. The CONTRACTOR should bear in mind that time is the essence of this agreement. Request for revision of construction time after tenders are opened will not be considered. The above period of ten days is included within the overall

COMPLETION SCHEDULE but not over and above the completion time to any additional work or any other reason.

8. Whenever any claim against the CONTRACTOR for the payment of a sum of money arises out or under the CONTRACT, the OWNER shall be entitled to recover such sum by appropriating in part or whole the Security Deposit of the CONTRACTOR. In the event of the security being insufficient or if no security has been taken from the CONTRACTOR, then the balance or the total sum recoverable, as the case shall be deducted from any sum then due or may become due thereafter at any time to the CONTRACTOR. The CONTRACTOR shall pay to the OWNER on demand any balance remaining due.
9. The contractor shall provide and maintain an office at the site for the accommodation of his agent and staff and such office shall be open at all reasonable hours to receive Instructions, notice or other communications. THE CONTRACTOR at all time shall maintain a site instruction book and compliance of these shall be communicated to the Engineer-in-charge from time to time and the whole document to be preserved and handed over after completion of works.
10. No part of the CONTRACT not any share or interest therein shall in any manner or degree be transferred, assigned or sublet by the CONTRACTOR directly or indirectly to any person, firm or corporation what so ever without the consent in writing, of the OWNER except as provided for in the succeeding sub-clause.
11. The CONTRACTOR agrees to and does hereby accept full and exclusive liability for the payment of any and all Taxes, Duties, including Excise Duty, Octrois, service Tax, Vat, Labour cess etc. now or hereafter imposed, increased, modified, all the sales taxes, duties, octrois etc. now in force and hereafter increased imposed or modified from time to time in respect of WORKS and materials and all contributions and taxes for unemployment compensation, insurance and old-age pensions or annuities now or hereafter imposed by any Central or State Government authorities which are imposed with respect to or covered by the wages, salaries or other compensations paid to the persons employed by the CONTRATOR and then CONTRACTOR shall be responsible for the compliance with all obligations and restrictions imposed by the Labour Law or any other law affecting employee relationship and the CONTRACTOR further agrees to comply, and to secure the compliance of all SUB-CONTRACTORS, with all applicable Central, State Municipal and local law and regulation and requirement of any Central, State or Local Government agency or authority. CONTRACTOR further agrees to defend, indemnify and hold OWNER harmless from any liability or penalty which may be imposed by the Central. State or local Authorities by reason or any violation by CONTRACTOR or SUB-CONTRACTOR of such laws, regulations or requirements and also from all claims, suits or proceedings that may be brought against the OWNER arising under, growing out of or by reason of the work provided for by this CONTRACT by third parties, or by Central or State Government authority or any administrative sub-division thereof.
- 13 Tax deductions will be made as per the rules and regulations in force in accordance with acts prevailing from time to time.
- 14 Tenderer should quote all inclusive prices including the liability of VAT/ Service Tax / Sales Tax/Turnover Tax, labour cess etc. whether on the works contract as a whole or in respect of bought out components used by the CONTRACTOR in execution of the CONTRACT. OWNER shall not be responsible for any such liability of the CONTRACTOR in respect of this CONTRACT.

- 15 The contractor shall carry out the various tests as enumerated in the technical specification of this tender document and the technical documents that will be furnished to him during the performance of the work and no separate payment shall be made unless otherwise specified in schedule to rates.
- 16 All the tests either on the field or at outside laboratories concerning the execution of the work and supply of materials by the Contractor shall be carried out by Contractor at his own cost.
- 17 Water to be provided at single point at free of cost from where contractor will make his own arrangement for temporary distribution. The point of supply will not be more than 500 meter. The owner shall not however guarantee the supply of water and no compensation for any failure or short supply of water will be entertained and in this respect contract should arrange water at his own cost.
- 18 The CONTRACTOR, on or after award of the WORK shall name and depute a qualified Engineer having sufficient experience in carrying out work of similar nature, to whom the equipments, materials, if any, shall be issued and instructions for works given the CONTRACTOR shall also provide to the satisfaction of the ENGINEER-IN-CHARGE sufficient and qualified staff to superintended the execution of the WORK Competent sub-agents, foremen and leading hands including those specially qualified be previous experience to supervise the type of work comprised in the CONTRACT in such manner as will ensure work of the best quality, expeditious working.
- 19 It is not permitted to shut down more than one toilet at a time in each floor to execute the job. If a ladies toilet is in running condition then no permission will be given to work in the adjacent gents' toilet. The CONTRACTOR should be competent enough to work in the night shift or in weekends to complete the job in time.
- 20 Any dispute arising under the agreement shall be referred to the arbitration to a sole Arbitrator appointed with the consent of the owner and the contractor as indicated in the article of the general conditions. The award of the arbitrator shall be final & binding on both parties.
- 21 Contractor should note that the quantities mentioned in BOQ may vary. However, contractor should take prior approval from the Engineer in charge for execution of any item in excess of the quantity mentioned in BOQ.
- 22 The contractor has to execute the job as per clients' priority and as instructed by Engineer in Charge.

The contractor should note that his workers must wear personal protective equipments (PPEs) such as safety helmet, safety goggles, hand gloves, safety shoes/ gum boots while performing a job. No workers will be allowed to work at site if found compromising with safety norms.

N.B. This project is an important project. This work has to be completed positively within stipulated time from the date of placement of LOI / work order. The selected Contractor has to make necessary provision for manpower, materials, machinery to complete the work as per schedule on round the clock basis without keeping provision for any holiday.

BOQ for Miscellaneous rearrangement & repairing works within office & store room at roof in WECS building

Sl No.	Description	UOM	Qty.	Rate (inclusive of GST and labour cess)	Amount
1	Dismantling carefully partition wall / doors(wooden framework, post, PVC panel) without damaging the false ceiling and other furnitures, including removal of dismantled materials (excepting the doors) out of premises and disposed to specified dumping area in conformity to Municipal laws	Sqm	55		
2	Taking out shutter of door and window, dismantling by parts (for repair or replacement of damaged parts), reassembling and refitting and rehangng same with old fittings but with new screws as necessary	Sqm	8		
3	Dismantling R.C. floor, roof, beams etc. including cutting rods and removing rubbish out of premises and disposed to specified dumping area in conformity to Municipal laws at all floors	Cum	1		
4	Applying Acrylic Emulsion Paint of approved make and brand on walls and ceiling including sand papering in intermediate coats including minor putty work (to be done under specific instruction of Superintending Engineer) standard quality one coat any shade, all floors	Sqm	130		
5	Supplying, fitting and fixing of false ceiling framework with powder coated exposed G.I. grid suspension system (E-Grid T 2430/1510 or equivalent load carrying capacity with mid span deflection not exceeding 1/360 span with hanger spacing of 1200mm c/c) consisting of Main Runner 3600 mm long, Cross Tee 1200 mm / 600 mm long and Wall Angle. The Wall Angle shall be fixed on PVC Dash Fasteners on the perimeter of the wall by steel screws with distance 300mm c/c. The Main Runners to be placed @ 1200 mm. The Cross Tee 1200mm will be inserted in the pre-cut slots of Main Runner at regular interval of 600 mm to form a modular grid of 1200mm X 600mm. Additional Cross Tees of 600 mm shall be placed perpendicular to the Cross Tee 1200 mm long to finally form a grid of 600 mm X 600 mm. Grid of module size 600 mm X 600	sqm	8		

	mm shall be supported by 6 mm dia G.I. wire from purlins / soffit. all complete as per drawing & directions of Engineer-in-charge. all floors				
6	Providing and fixing of false ceiling with powder coated exposed G.I. grid suspension system (E-Grid T 2430 or equivalent load carrying capacity with mid span deflection not exceeding 1/360 span with hanger spacing of 1200mm c/c) consisting of Main Runner 3600 mm long, Cross Tee 1200 mm / 600 mm long and Wall Angle. The Wall Angle shall be fixed on PVC Dash Fasteners on the perimeter of the wall by steel screws with distance 300mm c/c. The Main Runners to be placed @ 1200 mm. The Cross Tee 1200mm will be inserted in the pre-cut slots of Main Runner at regular interval of 600 mm to form a modular grid of 1200mm X 600mm. Additional Cross Tees of 600 mm shall be placed perpendicular to the Cross Tee 1200 mm long to finally form a grid of 600 mm X 600 mm. Grid of module size 600 mm X 600 mm shall be supported by 6 mm dia G.I. wire from purlins / soffit. 6 mm thick High Pressure Steam Cured Non Asbestos Fibre Cement Standard Ceiling Board (Density > 1300 Kg/m3) of size 595 mm X 595 mm, conforming IS 14862 & Type B Category III of ISO 8336, tested as per AS-1530 part 3 & BS-476 Part 4,5,6,7 & 8, should be placed in the Grid module to form a False Ceiling. All complete as per the drawing & directions of Engineer-in-charge. All floors False Ceiling (with 6mm thick Fibre Cement Designer Board and E-Grid T2430)	Sqm	5		
7	M.S. door as per approved design made of strong M.S. frame work, intermediate stiffeners and round / square bars or angles. M.S. sheet (not less than 14 gauge) gussets, cleats etc. including necessary riveting, bolting, welding, locking and hanging arrangements, fitting and fixing complete as per direction of the Engineer-in -charge. at all floors	Qntl	0.75		
8	Supplying fitting and fixing door frame with M.S. angle (50 mm x 50 mm x 6 mm) as per drawing & direction of required section. The holes for counter sunk machine screw & nuts will be such as to fit 8 to 10 mm Iron screw. The counter sunk nut to be welded . The nuts are to be welded after careful checking with	Kg	30		

	screw.All welding spots should be properly filed or rounded smooth including cost of welding hinges for hinge cleats , lugs for hasp bolt, socket bolt etc. and necessary M.S. clamps of 25mm x 6mm flat 225mm long as per direction welded to the frame fitted and fixed in position including cost of concrete at all floors				
9	Supplying best Indian sheet glass panes set in putty and fitted and fixed with nails and putty complete. (In all floors) 4 mm thick	Sqm	10		
10	Easing, oiling and adjusting the steel shutters including scraping all members and fitting so as to make the shutters easily operable (no extra payment will be made for taking out and fixing glass, if necessary). each pair means two shutters in a frame all floors	Pair	20		
11	Removing old scales, blisters, greasy soot from smoke affected walls etc. of interior surface of walls,ceiling by scraping etc. and preparing smooth and even surface with rendering or cement mortar (1:2) (as necessary), to make the surface suitable for receiving distemper. (Payment against this item will be made only when this has been done on the specific direction of the Engineer-in-charge). all floors	Sqm	40		
12	White washing including cleaning and smoothening surface thoroughly 3 coats	Sqm	40		
13	Labour for taking out door and window frame including shutter for repair or replacement of different parts of the frame & refixing the same including mending good all damaes complete. (Concrete and brick work for mending damage will be paid separately)	Sqm	2.5		
14	Supplying 'Godrej' mortice lock chromium plated with latch and keys 4 levers, including fitting and fixing complete.	Each	1		
15	Godrej Hydraulic door closer fitted and fixed complete heavy type	Each	3		
16	Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish	Cum	1		
17	Supplying solid flush type doors of commercial quality, the timber frame consisting of top and bottom rails and side styles of well seasoned timber 65mm wide	sqm	1.9		

	each and the entire frame fitted with 37.5mm wide battens places both ways in order to make the door of solid core and internal lipping with Garjan or similar wood veneers using phenol formaldehyde as glue etc. complete, including fitting, fixing shutters in position, including the cost of 3 butt hinges (75mm. X 60mm. X 3.15mm) and other fittings (like one skeleton bolt 225mm long x 10mm dia., one aluminium D handle 100 mm x 10 mm dia). all floors				
18	Wood work in door and window frame fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame including cost of concrete, Iron Butt Hinges and M.S clamps (8 nos per frame, 40mm X 6mm, 125mm Length). (The quantum should be corrected upto three decimals). other local wood	Cum	0.08		
19	Taking out existing partition/ceiling of particle board, masonite board, ply board, soft board etc. of any thickness and refixing same in new position with necessary clamps making holes in walls, floor, roof and mending damages if any	Sqm	3		
A.	Total amount including applicable GST & labour welfare cess=				

Total amount in words: